



काठमाडौं उपत्यका खानेपानी लिमिटेड

महाकालचौर शाखा



चलानी नं. ३९६/०८५/०८२

मिति २०८२/०३/०४

श्री सूचना प्रविधि शाखा

काठमाडौं उपत्यका खानेपानी लिमिटेड

मुख्य कार्यालय त्रिपुरेश्वर ।

विषय : वेभसाईटमा सूचना प्रकासन गरिदिने सम्बन्धमा ।

उपरोक्त सम्बन्धमा यस शाखा अन्तर्गत बू.न.पा. वडा नं. ११ गुरुङ्ग टोल क्षेत्रमा खानेपानीको ३ ईन्च HDPE पाईपलाईन बिस्तार कार्य मिति २०८२/०३/०१ मा सदर भए बमोजिम आ.व. २०८१/०८२ असार मसान्त भित्र कार्य गर्ने गरि BOQ, Design र Drawing लाई तीन दिनको म्याद राखी दररेट पेश गर्न यो सूचना कम्पनीको वेभसाईटमा मिति २०८२/०३/१६ गते ५:०० बजेसम्म दर्ता हुने गरि सूचित भएका निर्माण व्यवसायीबाट दररेट Hard copy माफत माग गर्ने व्यवस्थाको लागि मिति २०८२/३/४ गते सूचना प्रकासन गरिदिन हून अनुरोध छ ।

दररेट पेश गर्ने ठेगाना : का.उ.खा.पा.लि. महाकालचौर प्राविधिक फांट

सम्पर्क व्यक्ति :- रोशनी खत्री, मो.नं. ९८६८७०३४४२

बोधार्थ :

श्रीमान प्रमुख कार्यकारी अधिकृत ज्यू

काठमाडौं उपत्यका खानेपानी लिमिटेड

मुख्य कार्यालय त्रिपुरेश्वर ।


(ई. मिलन थापा)
कार्यालय प्रमुख

मुख्य कार्यालय, त्रिपुरेश्वर मार्ग, काठमाडौं
फोन नं. ४११७३५८/४११७३५९
फ्याक्स नं.: ००८७-१-४११७३५३
www.kathmanduwater.org

महाकालचौर शाखा
फोन नं. ५२१०३५७/५२१०१४३



KATHMANDU UPRATYAKA BHANJYAN LIMITED
MAHANKALCHAUR
BOQ

Project: 90 mm dia. and 63 mm dia. HDPE Pipeline Extension Works,
Location: Bu.Na.Pa.11, Gurung tole

S.N.	DESCRIPTION OF WORKS	QUANTITY	UNIT	RATE		AMOUNT	REMARKS
				IN FIGURE	IN WORDS		
	Part-A (Pipes and Materials)						
1	90 mm dia PN 10 HDPE Pipe	60.00	rm				
2	63 mm dia PN10 HDPE pipe	245.00	rm				
3	90mm *50 mm HDPE Tee	5.00	no				
4	Rubber Washer	1.00	no				
5	90 mm HDPE Plug	1.00	no				
6	63 mm HDPE Plugs	5.00	no				
	Part-B (Civil Works)						
1	Removing and Relaying of PCC Interblock(Using Old)	18.00	m2				
2	Dismantalling works of PCC Road	6.00	m3				
3	Earthwork excavation in Boulder mix soil for Pipe laying. Installation of Sluice valves and other fittings as per the instruction of site incharge.	150.00	m3				
4	Laying and Jointing of 90 mm HDPE pipe with joining all complete works	60.00	rm				
5	Laying and Jointing of 63 mm HDPE pipe with joining all complete works	245.00	rm				
6	PCC (1:2:4) works for Reinstate of Road	6.00	m3				
7	Back filling with proper compaction of parent soil (Boulder mixed) as per the instruction of site incharge	150.00	m3				
	Sub Total						
	Vat 13%						
	Grand Total						
	In words :Nrs.						

Name of Contractor:
Address:
Signature and Stamp:
Date: