



KATHMANDU UPATYAKA KHANEPANI LIMITED
MAHANKALCHAUR BRANCH OFFICE
QUOTATION



Project: 90 mm dia. and 63 mm dia HDPE Pipeline Extension Works.

Location: Akatamarga

Location: Akatamarga

S.N.	DESCRIPTION OF WORKS	QUANTITY	UNIT	RATE		AMOUNT	REMARKS
				IN FIGURE	IN WORDS		
	Part-A (Pipes and Materials)						
1	90 mm dia PN 10 HDPE Pipe	200.00	rm				
2	63 mm HDPE pipeline	30.00	rm				
3	110 mm *110 mm*90 mm HDPE TEE	2.00	no				
4	90 mm *63 mm HDPE Reducer	1.00	no				
5	90 mm Sluice valve	2.00	no				
6	80 mm OD Flange	2.00	no				
7	80 mm UPVC Mechanical Couplings	4.00	no				
8	80*150 mm long GI Nipple	4.00	no				
9	Rubber Washer	1.00	rm				
10	16 mm Nut Bolt	32.00	no				
11	50 mm End plug	1.00	no				
	Part-B (Civil Works)						
1	Dismantalling works of Asphalt Road	48.00	m2				
2	Dismantalling works of RCC Road	5.40	m3				
3	Earthwork excavation in Boulder mix soil for Pipe laying, Installation of Sluice valves and other fittings as per the instruction of site	110.40	m3				
4	Laying and Jointing of 110 mm HDPE pipe with joining all complete works	200.00	rm				
5	Laying and Jointing of 63 mm HDPE pipe with joining all complete works	30.00	rm				
6	Installation of Pipes,Fittings including cutting, threading, tapering etc.						
6.01	80 mm sluice valve	2.00	no				
6.02	80 mm Mechanical Couplings	4.00	no				
6.03	80 mm GI Fittings	6.00	no				
7	PCC (1:2:4) works for Reinstate of Road	10.20	m3				
8	Back filling with proper compaction of parent soil (Bouler mixed) as per the instruction of site Incharge	110.40	m3				
	Sub Total						
	Vat 13%						
	Total Project Cost						
	In words :Nrs.						

Name of Contractor:
Address:
Signature and Stamp:
Date:



KATHMANDU UPATYAKA KHANEPANI LIMITED
MAHANKALCHAUR BRANCH OFFICE
QUOTATION



Project: 110 mm dia. and 63 mm dia HDPE Pipeline Extension Works.

Location: santimarga

S.N.	DESCRIPTION OF WORKS	QUANTITY	UNIT	RATE		AMOUNT	REMARKS
				IN FIGURE	IN WORDS		
	Part-A (Pipes and Materials)						
1	110 mm dia. PN 10 HDPE Pipe	210.00	rm				
2	63 mm HDPE pipeline	50.00	rm				
3	110 mm *110 mm*63 mm HDPE TEE	5.00	no				
4	110 mm End Plug	1.00	no				
5	50 mm End plug	5.00	no				
	Part-B (Civil Works)						
1	Dismantalling works of Asphalt Road	114.00	m2				
2	Earthwork excavation in Boulder mix soil for Pipe laying, Installation of Sluice valves and other fittings as per the instruction of site	124.80	m3				
3	Laying and Jointing of 110 mm HDPE pipe with joining all complete works	210.00	rm				
4	Laying and Jointing of 63 mm HDPE pipe with joining all complete works	50.00	rm				
5	PCC (1:2:4) works for Reinstatement of Road	11.40	m3				
6	Back filling with proper compaction of parent soil (Boulder mixed) as per the instruction of site Incharge	124.80	m3				
	Sub Total						
	Vat 13%						
	Total Project Cost						
	In words :Nrs.						

Name of Contractor:
 Address:
 Signature and Stamp:
 Date:



KATHMANDU UPATYAKA KHANEPANI LIMITED
MAHANKALCHAUR BRANCH OFFICE
QUOTATION



Project: 110 mm dia. and 63 mm dia HDPE Pipeline Improvement Works.

Location: Pragati tole gate to santimarga gate, Sherpa chowka

S.N.	DESCRIPTION OF WORKS	QUANTITY	UNIT	RATE		AMOUNT	REMARKS
				IN FIGURE	IN WORDS		
	Part-A (Pipes and Materials)						
1	110 mm dia PN 10 HDPE Pipe	150.00	rm				
2	63 mm HDPE pipeline	50.00	rm				
3	50 mm CI Sluice Valve	1.00	no				
4	100 mm CI Sluice Valve	2.00	no				
5	50 mm HDPE Flange set With Adopter	1.00	no				
6	100 mm OD flange Set	2.00	no				
7	100 mm UPVC Mechanical Coupling	6.00	no				
8	110 mm *110 mm*63 mm HDPE TEE	1.00	no				
9	110 mm *110 mm*110 mm HDPE TEE	1.00	no				
10	100mm *150 mm GI Nipple	4.00	no				
11	50 mm *150 mm Gi Nipple	2.00	no				
12	50 mm UPVC Mechanical Couplings	2.00	no				
13	50 mm End plug	1.00	no				
14	Rubber Washer	2.00	rm				
15	16mm Nut Bolts	40.00	no				
	Part-B (Civil Works)						
1	Dismantalling works of Asphalt Road	84.00	m2				
2	Dismantalling of RCC Roads	2.70	m3				
3	Earthwork excavation in Boulder mix soil for Pipe laying, Installation of Sluice valves and other fittings as per the instruction of site	98.70	m3				
4	Laying and Jointing of 110 mm HDPE pipe with joining all complete works	150.00	rm				
5	Laying and Jointing of 63 mm HDPE pipe with joining all complete works	50.00	rm				
6	Installation of Pipes,Fittings including cutting, threading, tapering etc.						
6.01	100 mm sluice valve	2.00	no				
6.02	50 mm CI Sluice Valve	1.00	no				
6.03	100 mm Mechanical Couplings	6.00	no				
6.04	50 mm UPVC Mechanical Couplings	2.00	no				
6.05	100 mm GI Fittings	6.00	no				
6.06	50 mm GI Fittings	3.00	no				
7	PCC (1:2:4) works for Reinstatement of Road	11.10	m3				
8	Back filling with proper compaction of parent soil (Boulder mixed) as per the instruction of site Incharge	98.70	m3				
Sub Total							
Vat 13%							
Total Project Cost							
In words :Nrs.							

Name of Contractor:
 Address:
 Signature and Stamp:
 Date:



KATHMANDU UPATYAKHA KALA NIPANI LIMITED
MAHANKALCHAUR BRANCH OFFICE
QUOTATION

Project: 90 mm dia. and 63 mm dia HDPE Pipeline Extension Works.

Location: Bhadratole, Gyanprakash marga, Dhalanemarga

S.N.	DESCRIPTION OF WORKS	QUANTITY	UNIT	RATE		AMOUNT	REMARKS
				IN FIGURE	IN WORDS		
	Part-A (Pipes and Materials)						
1	90 mm dia.PN 10 HDPE Pipe	80.00	rm				
2	63 mm HDPE pipeline	340.00	rm				
3	110 mm *110 mm*90 mm HDPE TEE	4.00	no				
4	50 mm Sluice valve	4.00	no				
5	50 mm flange set with adopter	8.00	no				
6	50 mm UPVC Mechanical Couplings	4.00	no				
7	80 mm *80 mm *50 mm HDPE Tee	4.00	no				
8	50*150 mm long GI Nipple	8.00	no				
9	Rubber Washer	1.50	rm				
10	16 mm Nut Bolt	32.00	no				
11	50 mm End plug	4.00	no				
	Part-B (Civil Works)						
1	Dismantalling works of Asphalt Road	12.00	m2				
2	Dismantalling works of RCC Road	5.28	m3				
3	Earthwork excavation in Boulder mix soil for Pipe laying, Installation of Sluice valves and other fittings as per the instruction of site	176.40	m3				
4	Laying and Jointing of 90 mm HDPE pipe with joining all complete works	80.00	rm				
5	Laying and Jointing of 63 mm HDPE pipe with joining all complete works	340.00	rm				
6	Installation of Pipes,Fittings including cutting, threading, tapering etc.						
6.01	50 mm sluice valve	4.00	no				
6.02	50 mm Mechanical Couplings	4.00	no				
6.03	50 mm GI Fittings	8.00	no				
7	PCC (1:2:4) works for Reinstatement of Road	5.28	m3				
8	Back filling with proper compaction of parent soil (Boulder mixed) as per the instruction of site Incharge	176.40	m3				
	Sub Total						
	Vat 13%						
	Total Project Cost						
	In words :Nrs.						

Name of Contractor:
Address:
Signature and Stamp:
Date:



KATHMANDU UPATYAKA KRIYA PANEL LIMITED
MAHANKALCHATE BRANCH OFFICE
QUOTATION



Project: 90 mm dia. and 63 mm dia HDPE Pipeline Extension Works.

Location: Aanadbasti

Location: Karamadur

S.N.	DESCRIPTION OF WORKS	QUANTITY	UNIT	RATE		AMOUNT	REMARKS
				IN FIGURE	IN WORDS		
	Part-A (Pipes and Materials)						
1	90 mm dia PN 10 HDPE Pipe	40.00	rm				
2	63 mm HDPE pipeline	190.00	rm				
3	110 mm *110 mm*90 mm HDPE TEE	2.00	no				
4	90 mm *63 mm HDPE Reducer	1.00	no				
5	90 mm Sluice valve	1.00	no				
6	80 mm OD Flange	1.00	no				
7	80 mm UPVC Mechanical Couplings	2.00	no				
8	80*150 mm long GI Nipple	4.00	no				
9	Rubber Washer	1.00	rm				
10	16 mm Nut Bolt	32.00	no				
11	50 mm End plug	1.00	no				
	Part-B (Civil Works)						
1	Dismantalling works of Asphalt Road	54.00	m2				
2	Earthwork excavation in Boulder mix soil for Pipe laying, Installation of Sluice valves and other fittings as per the instruction of site incharge	110.40	m3				
3	Laying and Jointing of 90 mm HDPE pipe with joining all complete works	40.00	rm				
4	Laying and Jointing of 63 mm HDPE pipe with joining all complete works	190.00	rm				
5	Installation of Pipes,Fittings including cutting, threading, tapering etc.						
5.01	80 mm sluice valve	2.00	no				
5.02	80 mm Mechanical Couplings	2.00	no				
5.03	80 mm GI Fittings	5.00	no				
6	PCC (1:2:4) works for Reinstatement of Road	5.40	m3				
7	Back filling with proper compaction of parent soil (Boulder mixed) as per the instruction of site Incharge	110.40	m3				
	Sub Total						
	Vat 13%						
	Total Project Cost						
	In words :Nrs.						

Name of Contractor:
Address:
Signature and Stamp:
Date:



काठमाण्डौ उपत्यका खानेपानी लिमिटेड

महाकालचौर शाखा



मिति २०८२।०३।१८

चलानी नं. ४४६६१०८१/०८२

श्री सूचना प्रविधि शाखा

काठमाण्डौ उपत्यका खानेपानी लिमिटेड

मुख्य कार्यालय त्रिपुरेश्वर ।

दररेट दोरिबल गर्ने अखिल

अवधि - २०८२/०३/२३

नेपाली ११:०० (०४:००)
English ३ (२४hr) (१२hrs)

विषय : वेबसाईटमा सूचना प्रकासन गरिदिने सम्बन्धमा ।

उपरोक्त सम्बन्धमा यस शाखा अन्तर्गत तपशिल बमोजिम बुढानिलकण्ठ नगरपालिका बाट बजेट सुनिश्चता भए पश्चात, मिति २०८२।०३।१७ मा सदर भए बमोजिम आ.व. २०८१/०८२ असार मसान्त भित्र कार्य गर्ने गरि BOQ, Design र Drawing लाई तीन दिनको म्याद राखी दररेट पेश गर्न यो सूचना कम्पनीको वेबसाईटमा मिति २०८२।०३।२० गते ४:०० बजेसम्म दर्ता हुने गरि सूचिकृत भएका निर्माण व्यवसायीबाट दररेट Hard copy माफत माग गर्ने व्यवस्थाको लागि मिति २०८२।०३।१८ गते सूचना प्रकासन गरिदिन हन अनुरोध छ ।

तपशील

क्र.स.	विवरण
१	110 mm and 63 mm dia HDPE Pipeline Improvement works at pragati tole to santinagar gate
२	110 mm and 63 mm dia HDPE Pipeline Improvement works at santimarga
३	110 mm and 63 mm dia HDPE Pipeline Improvement works at Akatamarga
४	90 mm and 63 mm dia HDPE Pipeline Improvement works at Anandbasti
५	90 mm and 63 mm dia HDPE Pipeline Improvement works at Bhadratole, Gyanprakash marga, Dhalanemarga

दररेट पेश गर्ने ठेगाना : का.उ.खा.पा.लि. महाकालचौर प्राविधिक फांट

बोधार्थ :

श्रीमान प्रमुख कार्यकारी अधिकृत ज्यू

काठमाण्डौ उपत्यका खानेपानी लिमिटेड

मुख्य कार्यालय त्रिपुरेश्वर ।

.....

.....

(ई. मिलन था
उप-प्रबन्धक
कार्यालय प्रमु.)

(ई. मिलन थापा)
उप-प्रबन्धक
कार्यालय

मुख्य कार्यालय, त्रिपुरेश्वर मार्ग, काठमाण्डौ

फोन नं. ४११७३५८/४११७३५९

फ्याक्स नं.: ००९७-१-४११७३५३

www.kathmanduwater.org

महाकालचौर शाखा

फोन नं. ५२१०३५७/५२१०१४३